

# PARISH OF ASCENSION

## BUILDING DEPARTMENT



### SEQUENCE OF INSPECTIONS FOR NEW RESIDENCE ON PIERS

House Wrap (Brick)

House Wrap (Stucco)

House Wrap (Hardi/Vinyl)

House Wrap (All)

Temporary Meter

THESE INSPECTIONS CAN BE SCHEDULED AT ANY TIME DURING THE CONSTRUCTION PROCESS. HOUSE WRAP INSPECTIONS MUST BE DONE BEFORE INSTALLING EXTERIOR COVERINGS.

1.) Foundation

**\*\*SLAB CAN BE Poured AT THIS POINT\*\***

2.) Foundation on Piers (Inspection for Floor Framing and Anchoring)

3.) Plumbing Rough-in

4.) Plumbing Top-out (GAS IF APPLICABLE)

5.) Electrical Rough-In

6.) Mechanical Rough-In

NO SPECIFIC ORDER FOR THESE INSPECTIONS

7.) Framing

**\*\*INSULATION AND INTERIOR WALL COVERINGS CAN BE INSTALLED AT THIS POINT\*\***

8.) TCI (APPROVAL OF THIS INSPECTION WILL RELEASE PERMANENT POWER)

9.) Electrical Final

10.) Plumbing Final

11.) Mechanical Final

NO SPECIFIC ORDER FOR THESE INSPECTIONS

12.) Building Final

13.) Certificate of Occupancy

\*\*If any plumbing will be under the slab, please schedule a Plumbing Rough-In before the foundation inspection.

**\*\*TO SCHEDULE INSPECTIONS PLEASE CALL (225)450-1002\*\***